Gulf Intracoastal Waterway, Brazos River Floodgates and Colorado River Locks Feasibility Study

Inland Waterways Users Board Meeting No. 90


February 28, 2019 **Franchelle Craft- Project Manager**

"The views, opinions and findings contained in this report are those of the authors(s) and should not be construed as an official Department of the Army position, policy or decision, unless so designated by other official documentation." **US Army Corps** of Engineers





Brazos River Floodgates and Colorado River Floodgates - Project Location





STUDY PROBLEMS

- Modern barges/ships have to navigate through narrow 75ft. width alignments and outdated/narrow floodgates and locks that lead to <u>frequent accidents</u> that damage guidewalls and gates.
 - Outdated lock/floodgate construction at sector gates leads to structural, electrical and mechanical maintenance issues.
 - Shutdown of operations during high water periods and to repair strikes causes significant economic impacts to navigation industry.
- Any changes to sediment deposition into the GIWW will be assessed and included as additional O&M cost to the study.




WIDER AND DEEPER WATERWAYS ARE NARROW, SHALLOW CHANNELS AND OUTDATED FACILITIES COST BILLIONS IN DELAYS AND ARE POTENTIALLY DANGEROUS TO WORKERS. Many of the locks and dams in operation today were constructed during the 1930s.

The design life of locks and dams is generally 50 years and most of our locks have exceeded that.

Since 1970, vessel sizes have increased, affecting channel width and depth requirements


This spring, two bills were introduced in Congress – "Waterways are Vital for the Economy, Energy, Efficiency, and Environment Act" (WAVE 4, H.R. 1149) in the House and the "Water Resources Development Act" (WRDA, S.601) in the Senate – that address waterway concerns.

EVALUATION PROCESS




EVALUATION PROCESS

5



BRAZOS RIVER TSP ALTERNATIVE 3a.1

HYBRID Alternative – 125' Gates/Open West, Adjust Channel Angle




6

25' FLOOD GATE

REMOVE EXISTING 75' WIDE EAST AND WEST FLOODGATES CONSTRUCT NEW 125' WIDE EAST FLOODGATES AND OPEN CHANNEL ON WEST NEW FLOODGATES TO BE SETBACK FROM THE RIVER FOR LONGER APPROACH CHANNEL

CONSTRUCT NEW WING WALLS AND GUIDE WALLS FOR EAST FLOODGATES CONSTRUCT TEMPORARY BYPASS CHANNEL, BACKFILL WHEN CONSTRUCTION COMPLETE






POSED FLOOD GATE



COLORADO RIVER TSP ALTERNATIVE 4b.1

Convert both locks to 75' flood Riverside floodgates on both sides of crossing



NOTE: TAINTER GATE

NOTE: This drawing depicts the East and West Locks 75' Rivergates as already removed.





PROJECT AUTHORIZATION

Recommendation in Final Report

Brazos River Floodgates:

- Alternative 3a.1
 - 125' gates on the east side of channel
 - Open channel on west side of channel

Colorado River Locks:


 Authorization contingent upon the tonnage volume reaching a predetermined amount to be agreed upon prior to the signing of the Chief's Report

> NOTE: TAINTER GATE NOT SHOWN





PROJECT FIRST COST (PROGRAM YEAR BUDGET FY 2019)



Benefit Cost Ratio The BCRs at 2.87% are:

System TSP - 3.25 BRFG- 5.03 CRL-1.65 The BCRs at 7% are:

System TSP- 1.63 BRFG- 2.75 CRL-0.77

110-0" CLEAR SO THE SAME BULKHEADS CAN BE

> PRÉSTRESSED-CONCRETI TRUNNION GROEP -----

NOTE: TAIKTER GATE NOT SHOWN





0.000

EL 270.00

BRFG & CRL STUDY MILESTONES

			Study Milestone Dates	
Activity		1a \$3M/3 YRs	1b \$3.1M/ 3YR, 2MO	
		3x3x3 Baseline study focus with limited modeling	Existing with limited additional Cost and Time	
Study Start		JUL 2016	JUL 2016	
Alternative Evaluation and Analysis	Alternatives Milestone	SEP 2016	SEP 2016	
Exemption	Exemption Approval by Senior Leaders	N/A	FEB 2017	
Alternative Evaluation and Analysis	Tentatively Selected Plan (TSP) Milestone	OCT 2017	OCT 2017	
Feasibility Level Analysis	Agency Decision Milestone	JUL 2018	JUL 2018	
	Feasibility Report Complete (Post DQC & ATR)	FEB 2019	MAR 2019	
	Senior Leader Panel	APR 2019	MAY 2019	
	S&A Review	APR-MAY 2019	MAY-JUN 2019	
	Chief's Report	JUL 2019	SEPT 2019	

